

# MICE Target Development

Chris Booth

Sheffield

8<sup>th</sup> June 2006

- Progress since last Collaboration Mtg.
  - Review of components
  - Assembly tests at RAL in April
  - Developments resulting from tests
  - Increased effort for target
- Plans & schedule June to November

# Components

- Stator body
- Ceramic tube
- Glass readout tube
- Target shuttle
- Ceramic bearings
- Electronics
- Frame, jack, bellows, gate-valve

# Stator (1)

- Stator body from Manchester not built to specs.
- Micro-surgery allowed insertion of ceramic tube!
- We have learned how to make all components for future stators in house.




## Stator (2)

- Coil winding company provided satisfactory sample.
- 30 coils purchased, to construct new stator.
- Coils wound in-house also satisfactory.
- Will try new cooling and potting techniques in near future.




# Ceramic tube

- Test flanges & dummy stator built at RAL.
- Indium vacuum seals tested.
- Pronounced satisfactory!



# Optical readout enclosure

- Quartz glass tube and flange procured.
- Flange machined, tube fixed with cryostat cement.



# Shuttle

- Oxford assembled shaft, target, alignment fin, stop, magnets, readout vane (see picture) – **many thanks!**
- Magnets, readout vane supplied by Sheffield.
- For prototype, shaft produced from steel tube rather than titanium.
- Assembly cleaned in Oxford, delivered direct to RAL.

# Control electronics

- Cards now rack-mounted.
- Extensive tests with prototype drive. Several hours pulsing at 0.3 Hz (10 A).
- Some reliability & noise problems are being addressed.



# Bellows




Chris Booth

University of Sheffield

10





Ceramic bearings

Indium seals


Support frame

Drive mechanism

Bellows

Gate valve

Beam pipe




# Assembly test: 24-28 April

- First time many parts came together:
  - Stator first connected to electronics 20<sup>th</sup>
  - Glass readout tube assembled 21<sup>st</sup>
  - Target shuttle finished morning of 24<sup>th</sup>
  - Some RAL parts and flanges not previously assembled.


# What did we learn?


1. Glass tube was very fragile!
  - Broken near metal flange.
  - Ground down and re-glued – vacuum tested ok.
  - New crack when tightened down onto full assembly.
  - Covered in epoxy! Amazingly, this appeared to seal ok!



## 2. Target shuttle was distorted

- Slot cut along thin-walled tube to take alignment vane caused shaft to distort.
- Vane was twisted and slightly off-axis at one end.
- Would not pass through ceramic bearing.
- Slot & hole in bearing machined out to allow shaft and vane to pass.
- Some play and roughness, but movement satisfactory.





Titanium target

Alignment fin

Stop

Magnets

Steel shaft

Optical readout vane

### 3. Indium seals did not work!

- Despite success with test pieces, could not pump down below  $3 \times 10^{-3}$  mbar.
- Flanges found to have too large diameter and chamfer; rebates incorrect so inadequate closure of seal.
- Attempts to seal with extra indium.
- Only partial improvement.
- Prevented vacuum quality checks with mass spectrometer.

## 4. Temperature sensitivity

- Operation of drive (power-off to hold position) caused deterioration in vacuum. (Only 10-15°C temperature rise.)
- Chilled water cooling (12°C) also worsened vacuum.
- Partial recovery on return to ambient temperature.
- Movement of ceramic tube disturbing (imperfect) seal?

## 5. Optical readout block did not fit

- Insufficient space for readout block around glass tube when drive in raised position.
- Large guide flange removed – appears not to be necessary.
- Flange could also be machined down to allow space.



Large flange →

## 6. Extremely difficult to align optics

- Higher refractive index of quartz tube?
- RAL restrictions on use of laser in hall.
- Adjustment system not suitable for 3D alignment in both position and angle

## 7. Shaft length checked - OK

- relative positions of target (raised) & gate valve, target (lowered) & beam-pipe, readout vane & top of tube etc were all correct.

# Solutions to problems

1 & 6 Delicate glass tube, difficult alignment

- Replace glass tube with steel plus flat glass windows
  - Robust, much simpler optics.
  - Redesign optical mounts to allow off-line alignment and accurate relocation.
  - Involve RAL engineer in design (in conjunction with Richard Nicholson).
  - Meeting yesterday in Sheffield.

## 2 Distorted shuttle shaft

- Oxford redesigned target shuttle
  - Target, shaft, stop, alignment fin machined out of single piece of titanium.
  - Cross-shaped (or square?) cross-section.
  - Strong, no tendency to twist.
  - Only magnets and readout fin to be added.
  - New (or modified) ceramic bearings will be required – design to allow insertion of shaft through lower bearing for easier assembly.
  - Some questions have just arisen as to whether the shaft can be machined to this design! The design is under review.

## 3 & 4 Leaks at indium seals

- Flanges for indium seals to be re-ground or re-made
  - Vacuum and temperature tests are being performed at RAL.
  - Importance of careful quality control
  - Vacuum & temperature cycling tests will also be performed in Sheffield
  - In longer term, consider need for bonded ceramic-metal.

# Conclusions of Tests

Despite problems, a lot was learned.

- Practical details of assembly for first time.
- Improved design of major components.
- **No proper vacuum tests.**
- **No reliability or vibration tests.**
- Review held (with ISIS) 16<sup>th</sup> May.
- Will repeat assembly in hall in July, full mechanical & electrical test in September.
- **Will not install in ISIS for June** – perform thorough off-line checks for October access.

# Increased Effort for Target Work

- Daresbury lab electronic engineer (Steve Griffiths)
  - High power driver electronics
    - Capacitor bank power supply
    - >100 A hex bridge using IGBTs
- Oxford workshop effort
  - Shuttle shaft construction
- Mechanical engineer (Martin Baldwin) (RAL)
  - Replacement chamber with optical windows
  - Readout alignment mounting (with RN at Sheff.)
- Sheffield Physicist/Engineer (advertise soon!)
  - Thermal modelling of stator – improved cooling
  - Electromagnetic modelling – more efficient drive?

## Plans & Schedule (1)

- Indium seal tests (RAL)
- Build new shaft (Oxford)
- Design/build top chamber/readout (Sheff/RAL)
- Build new stator (Sheffield)
- Vacuum tests (Sheffield)
- Optical isolation of control boards (Sheffield)
- Optical drive of hex bridge (Sheffield)
- Improved control & monitoring (Sheffield)
- Acceleration & temperature tests (in vacuum) (Sheffield)
- Reliability tests (Sheffield)
- **Mechanical test at RAL 17<sup>th</sup>-21<sup>st</sup> July**

## Plans & Schedule (2)

- Build & test IGBT hex bridge driver (Daresbury)
- Build second shaft (Oxford)
- Build second (improved?) stator (Sheffield)
- Build second top chamber/readout (Sheff/RAL)
- New quadrature board for optics (Sheffield)
- Improved controller hardware & software (Sheffield)
- ISIS interface boards (Sheffield)
- Temperature monitoring hardware & s/w (Sheffield)
- Acceleration tests (at 80 A) (Sheffield)
- Temperature, reliability tests (at 80 A) (Sheffield)
- **Mechanical & electrical test at RAL 18<sup>th</sup>-22<sup>nd</sup> September**
- **Installation in ISIS October**

